



Although ALLCO do not recommend fixing posts or plant through the top of Membrane roofs or decks if this is required then use a plinth detail provides the fixing by other trades are kept off the main deck flood area.  
ALLCO recommend that all plantwork fixings are kept independent of the membrane roof ideally through vertical surfaces such as parapets.

All Fixings must be sealed

NOTE: ALLCO and it's Approved Applicators do not warranty fixings installed by other trades.

1

## JM TPO - PLANTWORK FIXING PLINTH OPTIONS

SCALE: NTS



The information and data contained herein are believed to be accurate and reliable.  
This information does not constitute a warranty and should be used in conjunction with the project specification document supplied by Allco Waterproofing Solutions Ltd  
Please contact Allco Waterproofing Solutions Ltd with any questions or deviations from this information.  
© Allco Waterproofing Solution Ltd

For Technical Advice Contact:  
Web: [www.allco.co.nz](http://www.allco.co.nz)  
Email: [info@allco.co.nz](mailto:info@allco.co.nz)  
Telephone: 09 448 1185  
Facsimile: 09 448 1186



DRAWN BY:  
ALLCO

DATE:  
10/2020

DRAWING REF:  
T-016

REV:  
1